

BRUHAT BANGALORE MAHANAGARA PALIKE, BYATARAYAPURA ZONE**Executive Engineer
Byatarayanapura Division****B.B.M.P., Bangalore - 92****BBMP/2013-14/WT/WORK_INDENT7463****DRAFT TENDER SCHEDULE****Issued to :****Original / Duplicate****Drilling of borewells and providing pump and motor at Saraipalya, Nagawara and Rachenahalli SC Colony in ward no. 06, Byatarayanapura sub division.**

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging technical personal and labour required etc., as per Specification and direction (P.42, I. 9.4) PRED.SR 2011-12 Ashwathnagara	Each BW	1900	
2	1	Vidyasagara	Each BW	1900	
3	1	Akashvani Layout	Each BW	1900	
4	150	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.) P. 36 / I. 9.1 PRED SR 2010-11 0 to 50 m	Rmtr	287	
5	150	50 to 100 m	Rmtr	379	
6	150	100 to 150 m	Rmtr	422	
7	150	150 to 200 m	Rmtr	464	
8	150	200 to 250 m	Rmtr	513	
9	240	250 to 320 m	Rmtr	550	
10	210	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) SE PRED Approved Rate	Rmtr	1305	
11	54	Providing 250mm dia PVC Pipe 6kg/cm SE PRED Approved Rate	Rmtr	754.47	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
12	9	Providing 175mm dia M.S Collar SE PRED Approved Rate	Each	150	
13	3	Providing and fixing 160mm Borewell Cap with Clamp Set H/D	Each	695	
14	1	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required accessories such as suction, casing suction strainers sand guard Non return valve etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 20 stage. SE RDED Approved Rate 15 HP 30 Stage	No	52000	
15	2	17.50 HP 30 Stage	No	62550	
16	900	Supplying of ISI marked galvanized mild steel tube (continuously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes thraeftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendment 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008.	Rmtr	415	
17	156	Heavy Duty Collars	Rmtr	130	
18	2010	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-c(1) 2.5 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2010-11	Mtr	185	
19	3	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09	No	3000	
20	3	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 32/ I No. 2/f KPWD Electrical SR 2010-11	Each	285	
21	150	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.P No. 68/ I No. 4(d) 4 core 16 Sqmm KPWD Electrical SR 2010-11	Mtr	150	
22	150	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, P No. 69 / I No. 1a In existing trencg/duct 6Sqmm to 16 Sqmm) KPWD Electrical SR 2010-11	Mtr	8	
23	120	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB 1-2 P-7) P No. 70/ I. No. 6-c KPWD Electrical SR 2010-11 For Cutting Road Surface	Mtr	60	


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
24	12	Supplying and fixing of Class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 70/ I No.9-A KPWD Electrical SR 2010-11 40mm dia GI pipe	Mtr	240	
25	3	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 70/ I No. 10-b KPWD Electrical SR 2010-11 16Sqmm	No.	260	
26	3	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal proportion of salt and charcoal 150 mm around the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 through holes of 122 mm dia, (PWD Electrical SR-1999-2000, (P No.68, I No. 1) KPWD Electrical SR 2010-11	No	1950	
27	18	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3d KPWD Electrical SR 2010-11 100 Amps	No.	415	
28	3	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No. 82Item No. 13.55 / PWD SR 2010-11	Nos	1114.06	
29	3	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 84 / I. No. 13.81.3 PWD SR 2010-11	No	201.4	
30	3	Supplying TPST with rewirable porcelain channels in SM enclosure PRED SR 2010-11 P.32 item No. 1b Group A	No.	3050	
31	18	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading and labour charges etc complete	No	80	
32	3	Supplying shunt capacitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications	No	350	
33	3	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materials wiring complete as required 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications	No	1000	
34	90450	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 P.No. 41, I. No. 38B KPWD Electrical SR 2010-11	Sq.Cm	0.33	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
35	3	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. PRED Bangalore Circle SE Approved Date 30.07.2010 15HP to 30 HP Star Delta Starter	No.	10000	
36	3	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 (P.81/I.13.37 PWD SR - 2010-11)	Each	1582.58	
37	175.5	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2011-12	Cum	213.06	
38	325	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and including lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the excavation Etc.75MM 10 KSC Pvc Pipe Page No.14 item No.3.4.2 PRED SR 2011-12.	Rmtr	168	
39	175.5	Refilling the basement and pipeline trenches with selected available earth from trench excavation including watering consolidation in layers of 15 cm thick including disposing of the surplus earth with a lead of 200 meters Item No. 1.6 Page No.3 PRED SR 2011-12	Cum	65	

Signature of the Contractor


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಕೂಲ್‌ನ್ನು
ತಿರುಪ್ಪದಿಗಳ ಸಂಖ್ಯೆ 142
ತಿರುಪ್ಪದಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.


Superintending Engineer
Yelahanka Zone
BBMP, Bangalore - 92